

REQUISITION

Company: HWSETA

Location: KZN Office

Subject: Network Port Installation and AP Mounting

Supply and Installing of Network ports to HWSETA KZN Office.

Product	Quantity
Ethernet wall port	4
Mounting WiFi Access Points	2

Technical Specification:

Installation

- Installing physical ethernet wall ports in the office
- Mounting WiFi Access Points on the ceiling (**WiFi devices to be supplied by HWSETA**)

Cabling

- Running RJ45 CAT6 ethernet cable from WiFi AP to switch, server cabinet (approximately 20m and 50m)
- Running RJ45 CAT6 ethernet cables from newly installed physical ports in wall to patch panel, server cabinet.
- Trunking newly installed cables and labelling
- Trunking exposed existing cables and labelling

N.B We recommend that the supplier conduct a site inspection before submitting a quotation to ensure they understand the project requirements and costs.

Please find attached images of the current state of the office





